Bruhath Bangalore Mahanagara Palike Dasarahalli Zone

Name of Work: Construction of rooms and other civil works at Ambedkar Bhavan (Balance portion) in Mallasandra colony ward No 13 Shettyhalli Sub Division

SCHEDULE B

Sl No	Description	Unit	Qty	Approved Rate	
				In Figures (Rs)	In Words
1	Earth work excavation for foundation of building water sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of colds complete as per specifications.	Cum	130.72	484.92	Rupees Four Hundred Eighty Four And Paise Ninety Two Only
2	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil invoiving , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification	Cum	25.74	203.77	Rupees Two Hundred Three And Paise Seventy Seven Only
3	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	44.17	5698.58	Rupees Five Thousand Six Hundred Ninety Eight And Paise Fifty Eight Only
4	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specificationsdo- Wall & bottom thickness 15cm	Cum	10.43	7189.42	Rupees Seven Thousand One Hundred Eighty Nine And Paise Forty Two Only
5	Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size gradedgranite metal Coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms.thick, well compacted, in foundation, plinth and cills, including cost ofall materials, labour, HOM curing complete as per specifications.	Cum	10.14	5952.93	Rupees Five Thousand Nine Hundred Fifty Two And Paise Ninety Three Only
6	Providing and laying in position reinforced cement concrete cum of Design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70 cum and fine aggregtes @ 0.47cum, with super piasticisers @ 3 liters confirming to IS 9103-1999 reafirmed-2008 at machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspiliars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications.	Cum	51.12	6731.06	Rupees Six Thousand Seven Hundred Thirty One And Paise Six Only
7	Providing precast slab of 100 mm thick including cost of all materials, labour, curing,transportation, loading unloading,etc.,complete as per the direction of engineer in charge-	Sqm	6.30	2337.00	Rupees Two Thousand Three Hundred Thirty Seven Only
8	Providing precast slab of 250 mm thick including cost of all materials, labour, curing,transportation, loading unloading,etc.,complete as per the direction of engineer in charge-	Sqm	13.50	5418.00	Rupees Five Thousand Four Hundred Eighteen Only
9	Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/rrim2 confirming to JS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 \ including cost of ail materials labour charges, scaffolding, curing, hirecharges of machineries etc., complete as per specifications.	Sqm	360.30	1070.03	Rupees One Thousand Seventy And Paise Three Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER

Scanned with CamScanner

10	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 24kgs, with 12mm and down size graded granite metal coarse aggregates @0.05175cum and fine aggregtes @ 0.0345cum, with superplastisiser @0.225lts, machine mixed, well compacted for plain chajja of 7.5 cms average thickness, upto ground floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete but excluding cost of reinforcement as per specifications	Cum	13.68	490.32	Rupees Four Hund... Ninety And ...ise Thir... Two Only
11	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Ton	7.35	76643.28	Rupees Seventy Six Thousand Six Hundred Forty Three And Paise Twenty Eight Only
12	Providing and removing centering shuttering strutting propping etc., and removal of form work for columns, pillars, abutments, post and struts square/ rectangular/ polygon in plan including cost of all materials labour complete as per specification	Sqm	82.12	492.48	Rupees Four Hundred Ninety Two And Paise Forty Eight Only
13	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for suspended floors, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications for heights more than 3.50m from ground level.	Sqm	319.61	626.40	Rupees Six Hundred Twenty Six And Paise Forty Only
14	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams,beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour completeas per specifications.	Sqm	37.08	315.36	Rupees Three Hundred Fifteen And Paise Thirty Six Only
15	Providing and removing centering shuttering strutting propping etc., for chejjas, corbels etc., including edges including cost of all materials, labour complete as per specifications	Sqm	16.83	348.84	Rupees Three Hundred Forty Eight And Paise Eighty Four Only
16	Providing Honne wood frames of doors, windows, clerestory windows, ventilators and other frames wrought, framed of assembled including making plaster grooves (excluding cost of materials, labour, HOM of machineries complete as per specifications	Cum	0.78	94612.32	Rupees Ninety Four Thousand Six Hundred Twelve And Paise Thirty Two Only
17	Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 40mm, thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour,HOM of machineries completed as per specification (excluding cost of fixtures)	Sqm	10.80	5099.76	Rupees Five Thousand Ninety Nine And Paise Seventy Six Only
18	SOLID PANEL PVC DOOR SHUTTER Providing & fixing 30mm thick factory made rigid foam Panelled Door styles and 15x15mm for top & bottom rails, covered with heat moulded PVC channel of 5mm thick sheet & 30 x 50mm wide to form styles &5mm thick & 75mm wide PVC Sheets for top rail, lock rail & bottom rail oneither side & 5mm thick 20mm wide PVC sheet as gap insert for top rail & bottom rail, Panelling of 5mm thick PVC sheet fitted in the M.S. Frame, Sealed to the styles & rails with 5x30mm PVC sheet beading on either side & joined together with solvent cement adhesive etc., Complete as per manufacturers specification & direction of Engineer-in-charge fixed to frames with 3 nos of 75 mm Aluminium hinges.	Sqm	8.10	2999.16	Rupees Two Thousand Nine Hundred Ninety Nine And Paise Sixteen Only
19	Providing and fixing M.S. grill work for windows and ventilator weighing 21kg/Sqm using M.S. flats, or M.S square rods or combination of M.S. flats and steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures labour and HOM of machinery specifications	Kg	574.56	102.60	Rupees One Hundred Two And Paise Sixty Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahangara Palike,
Dasarahalli Division, Bengaluru-57

Scanned with CamScanner

	Providing and fixing in position collapsible steel shutters type with single rib diagonals 25mmx4mm size, with top and bottom rails of 2 nos and guide, locking arrangements, stoppers, handles on both sides with 2 Sqmm openings at 10 cms c to c applying a priming coat of red lead specifications, size of gate 3.4mx1.6m.	Sqm	5.44	4828.88	Rupees Four Thousand Six Hundred Twenty Six And Paise Eighty Only
21	Providing and fixing in position anodized aluminium windows and ventilators as per approved drawings with sliding shutters using double track window frame section of size 122.2x31.75mm with 1.2mm thick bottom section weight of 0.888 kg per m, sides and top section of 1.5mm thick weight of 0.650 kg per m and shutter comprising top and bottom section of size 40mmx18mm, 1.25mm thick of 0.417 kg per m shutter outer side 40mmx18mm, 1.25mm thick weight of 0.417 kg per m, shutter interior section 40mmx 26.7mm, 1.14mm thick weight of 0.403 kg per m the shutter mounted on nylon roller with approved quality of fixture such as aluminium tower bolts etc., and providing and fixing 5.5mm thick plain glass of shutter fitted with rubber beading aluminium section anodized 12 to 15 microns including cutting to required length, joints mitred sub dividing the frame tenonned rivetted in the assembled frame stiffened with send clips at corners angles etc., and fixed to walls, lintels, floor beams or cills as the case may be with necessary steel screws, rawl plugs, or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar, aluminium section are treated for	Sqm	36.28	4726.80	Rupees Four Thousand Seven Hundred Twenty Five Only
22	Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering providing and removing scaffolding including cost of materials, labour curing complete as per specification	Sqm	211.84	266.28	Rupees Two Hundred Fifty Six And Paise Twenty Eight Only
23	Providing 15mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering providing and removing scaffolding including cost of materials labour curing complete as per specifications	Sqm	478.08	301.80	Rupees Three Hundred One And Paise Eighty Only
24	Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour curing complete as per specifications	Sqm	887.92	34.56	Rupees Thirty Four And Paise Fifty Six Only
25	Providing 20mm thick cement plaster in single coat with cement mortar 1:3, to stone masonry & concrete surface including rounding off corners wherever required smooth rendering. Providing and removing scaffolding including cost of materials, labour curing complete as per specifications	Sqm	486.84	304.37	Rupees Three Hundred Four And Paise Thirty Seven Only
26	Providing and laying flooring using prepolished water cutrgang saw 18mm thick granite laid over bed of 20mm thick 1:4 cm & jointed with neat cement slurry mixed with pigment to match shade of granite slabs including laying POP on finished surface and cleaning the surface including the cost of all materials and labours etc., complete as per specifications. using silver grey granite / Multy Red / Ruby Red / Black / HassanGreen Granite of width not less than 1200mm	Sqm	408.84	2961.20	Rupees Two Thousand Nine Hundred Sixty One And Paise Twenty Only

EXECUTIVE ENGINEER-4
KRIDL, RAMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER
Bharat Sarige
Dasarahalli

Scanned with CamScanner

17	Providing and laying integral cement based water proofing treatment including preparation of surface as required for treatment of roofs, balconies terraces etc., consisting of following applications a) applying and grouting a slurry coat of neat cement using 2.75 kg per sqm of cement admixed with proprietary water proofing compound conforming to IS 2645 over the RCC slab after cleaning the surface before treatment b)laying cement concrete using broken brick bats 25mm to 100mmsize with 50% of cement mortar 1:5 admix with propreatory water proofing compound confirming IS 2645 over 20mm thick layer of cement mortar 1:5 admix with proprietary water proofing compound to required slope and treating similarly the adjoining walls upto 300mm height including rounding off junctions of walls and slabs c)after two days of proper curing applying a second coat of cement slurry admix with preprietoray water proofing compound d) finishing the surface with 20mm joint less cement mortar of mix 1:4 admix with preprietary water proofing compond wall finally finishing the surface with travel and neat cement slurry and making of 300 x 300 mm square e the whole terrace so finished shall be flooded	Sqm	195.91	1099.50	Rupees One Thousand Ninety Nine And Paise Fifty Only
18	Providing and fixing on wall surface 4.0kg/Sq.cm H.D.P.E. rain down water pipes 90mm outer dia approved make and brand with necessary specials like shoes, bends and offsets fixed with iron clamps, wall plugs, screws, including cost of materials, labour, complete as per specification	Rmt	42.00	414.46	Rupees Four Hundred Fourteen And Paise Forty Six Only
19	Providing and fixing to wall, ceiling and floor high density polyethylene pipes 6.00kgf/sq cm working pressure of outside diameter raising mains & exposed distribution pipes with special flangecompression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM and testing complete as per specifications	Rmt	65.00	785.46	Rupees Seven Hundred Eighty Five And Paise Forty Six Only
20	Providing and fixing white vitreous china clay, water closet Orissa pattern of size 580 x 440mm with integral type footrests,100mm S or P trap, 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I./M.S brackets, 32mm diameter flush pipe fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.	No	6.00	4561.92	Rupees Four Thousand Five Hundred Sixty One And Paise Ninety Two Only
21	Providing and fixing white vitreous china clay, water closet European type (Pedestal type, P-trap) with black solid plastic seat and lid, C.P brass hinges, rubber buffers. 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I./M.S brackets, 40mm diameter flush bend with fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.	No	6.00	5352.48	Rupees Five Thousand Three Hundred Fifty Two And Paise Forty Eight Only
22	Providing and fixing white vitreous china clay flat back wash basin size 630x450mm with a single of 15mm C.P. brass pillar taps with C.I. /M.S. brackets 32mm C.P. brass waste of standard pattern, painting of fittings and brackets, cuttings and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications	No	6.00	3400.92	Rupees Three Thousand Four Hundred And Paise Ninety Two Only
23	Providing and fixing white vitreous china clay, flat back, lipped front urinal basin of 430x260x350mm with 5 litre PVC automatic flushing cistren, C.I./M.S bracket, standard flush pipe and c.P. brass spreaders with brass union and G.I.Clamp Complete painting of fitting and brackets, cutting and making good the wall and floor wherever required , including cost of materials, labour complete as per specificabon	No	6.00	3317.76	Rupees Three Thousand Three Hundred Seventeen And Paise Seventy Six Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-57

Scanned with CamScanner

34	Providing skirting, dado, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications. Specification No.KBS 14.16, 14.17 - Colour glazed tiles 30x45 cms 6mm thick with border of size 30 x 10 cms.	Sqm	131.09	1764.62	Rupees One Thousand Seven Hundred Sixty Four And Paise Sixty Two Only
35	Providing Ceramic tiles of approved make,shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. Ceramic tiles 30x30 cm	Sqm	15.12	1309.28	Rupees One Thousand Three Hundred Nine And Paise Twenty Eight Only
36	Providing and fixing 7.5 cms to 15.00 cms dia NP grating 100 mm dia.	Each	24.00	162.00	Rupees One Hundred Sixty Two Only
37	Providing and fixing CI Nahani trap of approved make conforming to ISI specifications and construction of Cistern in M-15 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot). - 10cms x 7.5cms	Each	12.00	270.00	Rupees Two Hundred Seventy Only
38	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.) - 25mm nominal OD pipes	Rmt	60.00	316.44	Rupees Three Hundred Sixteen And Paise Forty Four Only
39	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.) - 32mm nominal OD pipes	Rmt	25.00	403.92	Rupees Four Hundred Three And Paise Ninety Two Only
40	Providing and fixing in position brass bib cock of approved quality nominal bore including cost of all materials, labour and HOM with all leads complete as per specifications.	Each	35.00	205.20	Rupees Two Hundred Five And Paise Twenty Only
41	providing and fixing in position brass gate valve with C.I. Wheel of approved quality (Screwed end) 20mm nominal bore including cost of all materials labour and HOM of Equipments with all lead complete as per specificatins	Each	22.00	362.88	Rupees Three Hundred Sixty Two And Paise Eighty Eight Only
42	Providing and fixing stainless steel kitchen sink of bowl depth 178mm, with drain board, M.S / C.I brackets, stainless steel plug 40 mm, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. size 510 x 1040 mm	No	4.00	15394.32	Rupees Fifteen Thousand Three Hundred Ninety Four And Paise Thirty Two Only
43	Providing and fixing in position brass stop cock of approved quality nominal bore including cost of all materials, labour and HOM with all leads complete as per specifications.15 mm dia nominal bore.	No	6.00	152.28	Rupees One Hundred Fifty Two And Paise Twenty Eight Only
44	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete. - for 32mm dia	Each	4.00	129.60	Rupees One Hundred Twenty Nine And Paise Sixty Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahangara Palike,
Dasarahalli Division, Bengaluru-57

Scanned with CamScanner

45	Constructing brick masonry inspection chamber 600x600mm, and 450mm depth, (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) 455x610mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23kg and weight of frame 15 kg) R.C.C. top slab with cement concrete M 15 with 20mm and downsize granite metal, foundation concrete M 5 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing complete as per specifications. Specification No. KBS 450x450mm and 450mm depth (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) 450x450mm	No	10.00	9169.20	Rupees Nine Thousar One Hundred Sixty Ni And Paise Twenty On
46	Providing and placing on terrace, polyethylene water storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications. (For 1000 litre capacity)	No	2.00	7374.24	Rupees Seven Thousar Three Hundred Seventy Four And Paise Twenty Four Only
47	Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications with primer	Sqm	1094.93	97.20	Rupees Ninety Seven And Paise Twenty Only
48	Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications with primer	Sqm	705.58	110.16	Rupees One Hundred Ten And Paise Sixteen Only
49	Applying priming coat over new wood surface and/ or wood based surface after preparing the surface after throughly cleaning oil, grease, dirt and foreign matter, sand papering and knotting liquid wood filler, for varnish including cost of materials, labour, complete as per specificatios	Sqm	55.28	54.00	Rupees Fifty Four Only
50	Providing and applying painting two coats (excluding priming coat) on new wood surface and/ or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications	Sqm	55.28	104.76	Rupees One Hundred Four And Paise Seventy Six Only
51	Applying red lead ready mix priming coat over new steel or other metal surface including preparing the surface after throughly cleaning oil, grease, dirt and other foreign matter, and scoured with wire brushes, fine steel wool, sand papers including cost of materials, labour, complete as per specifications	Sqm	32.40	44.28	Rupees Forty Four And Paise Twenty Eight Only
52	Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surfacebrushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications	Sqm	32.40	102.60	Rupees One Hundred Two And Paise Sixty Only
53	Providing and fixing to wall, ceiling and floor high density polyethylene pipes 6.00 kgf/sq cm working pressure 110mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications	Rmt	54.00	642.60	Rupees Six Hundred Forty Two And Paise Sixty Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike,
Dasarahalli Division, Bengaluru-57

Scanned with CamScanner

54	Fabricating, providing and erecting in position Hot dip galvanised Gate. Using 72 X 72 X 4.8mm Sq. GI Pipe Frame with Top pipe bending in heavy duty hydraulic press with sand packing and hot bending to form double arch as per drawing profile, 20mm hot dip galvanised sq. rod for verticals at 150mm c/c, as shown in the drawing including providing hot dip galvanised forged ornamental design in between sq. rods and heads at top, middle and bottom. Intermediate supports of 75X12 mm and 50X6 mm arch bend to hot dip galvanised flats. The work is inclusive of throughing GI flat GI sq. rods, placing, welding all the joints including grinding, finishing metal putty, painting two coats enamel painting. The rate is inclusive of all materials like GI sq. pipe, GI sq. rods, GI forged designs etc., heavy duty hinges are made out of 75mm solid sq. block assembled with 20mm dia bearing in three places for each flop. Heavy Duty Locking arrangements at tow places including cost of labour, painting, erecting charges using hoist pulley cranes with all lead and lift, loading, transportation, unloading, scaffolding charges and all other incidental charges for successful completion of the work as per directions	Sqm	17.44	12475.03	Rupees Twelve Thousand Four Hundred Seventy Five And Paise Three Only
55	Rectangalur shape mirror of size 1500x450mm with plastic moulded frame	No	10.00	1006.56	Rupees One Thousand Six And Paise Fifty Six Only
56	Providing and fixing self-supported, ribbed, high quality, high grade (D:350 MPAYst Min), pre- painted Galvalume steel roof sheet, coated with bare Galvalume coating AZ 150, @150 gms/Smtr 55%AL,45%Zn) by hot dip process , of total coated thickness as specified for different spans with a tolerance of+/- 0.02 mm, according to technical specification confirming to A 792, with NCCA11-1, or ECCAT4 Pencil hardness HB, NCCA standard T-Bend test. The roof should be fastened to the gutter beam, on the external sloping side, at an interval of 51mm Centre to Centre, to a depth of 65 mm with GI anchor bolts and neoprene washers & subjecting the gutter beam to Schmidt, Hammer test to ensure the anchorage of the anchor bolts. The self-supported roofing system should be designed to with stand the wind loacl (As per IS 875 part-3) & Earthquake load (as per IS 1893) & the design should also comply with any other technical requirements such as turbo ventilators of 0.60 mts. dia and skylights of size 4.26 x 0.60 mts. fixed one in each row @ 10.00 Mtr C/C along the length & hangers for electrical fixtures as per the requirements including cost of all materials &labour for erection, all lead and lift, loading and unloading, HOM of machineries etc., complete as per the standard	Sqm	123.00	1684.80	Rupees One Thousand Six Hundred Eighty Four And Paise Eighty Only
57	Fabrication supplying and erecting M.S. tubular trusses of all spans as quality material and are durable, reliable and corrosion and abrasion resistant. Welding shall confirm to latest structural welding code. Quality shall be on various parameters like shape, size, design gauge and polish. The entire trusses is anchored in RCC column by using 4 nos of M.S. anchor bolts at each support with 10mm thick base plate and shoe plate. The work includes cutting, straightening, placing in position of M.S. pipes and welding wherever necessary and applying one coat of redoxide primer coat to all the members including cost of all materials, labour charges, and hire charges of machineries for cutting, welding, grinding and erection equipments, with all lead and lift, transportation, letc., complete as per specification		1230.43	119.88	Rupees One Hundred Nineteen And Paise Eighty Eight Only
58	Providing and fixing stainless steel 304 grade for staircase railings, balconies, ramps, with hand rail, 50mm dia 16 guage hollow pipe welded to vertical hollow 50mm dia pipe of 16 guage, stainless steel vertical pipe spaced at 1.20m regular intervals and 5 Nos of 25mm dia. Stainless steel hollow horizontal pipe are welded to vertical 50mm dia hollow pipe. The entire assembly is fixed to staircase concrete by using expansion bolts by drilling concrete etc., complete including cost of materials, labour, HOM of and electrical charges, etc., complete as per specifications.	Sqm	17.00	6502.68	Rupees Six Thousand Five Hundred Two And Paise Sixty Eight Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike,
Basavanagudi Division, Bengaluru-57

Scanned with CamScanner

59	Manufacturing, supplying and fixing wooden ward robe of 0.60m deep using 19mm thick vinyl bonded water proof block board, shutters allround ward robe, lockable drawers with sliding channels, cupboard drapery hangers, curtain rods with end brackets, openable shutters with 19mm x 6mm thick plain teak wood beading, lipping 1.5mm thick commercial ply vertical support finished in approved 1 mm lamination sheet of approved colour, shade and quality on all exposed surfaces. Inner surface painted with 2 coats of white synthetic enamel paint over 2 coats of Patti, one coat of wood primer, including cost of brass fittings, parliamentary hinges, C handles, tower bolts, magnetic catches, approved brand lock, adhesives, synthetic resins, nails, screws etc., complete including cost of all materials, labour charges, complete as per specification	Sqm	15.75	11612.16	Rupees Eleven Thousand Six Hundred Twelve And Paise Sixteen Only
60	Providing and laying in position to required level or slope 230mm internal diameter salt glazed stone ware pipe grade A and joiting with stiff mixture of cement mortar in 1:1 testing of pipes and joiting, including cost of materials, labour chargea complete as per specification	Rmt	55.00	568.16	Rupees Five Hundred Sixty Eight And Paise Sixteen Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

Executive Engineer
Dasarahalli Zone
BBMP

Scanned with CamScanner